

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Larsen-Madera-Harrison, c/o Gabbert-Jones, Inc.

Complete Address: 830 Sutton Place, Wichita, Kansas

Lease Name Maas Well No. # 1

Location C NW NW Sec. 7 Twp. 27 Rge. 11 (E) (W) W

County Pratt Total Depth 4454

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Gabbert-Jones, Inc.

Address: 830 Sutton Place, Wichita, Kansas License No.

Operation Completed: Hour 10:00PM Day 28th Month Nov. Year 1966

The Above well was plugged as follows:

334' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged with
1/2 sack of hulls on fluid at 250', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack
of hulls on fluid at 40', and cemented with 10 sacks to the base of the
cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/6/66
INV. NO. 4400-U

Signed: Archie Elving
Well Plugging Supervisor