

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-14-71
APR 14 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Graham-Michaelis Drlg. Inc.

Complete Address Box 769 Woodward, OK

Lease Name Farley Well No. 4

Location C NW/NE Sec. 32 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4779

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 10:30 AM Day 12 Month 4 Year 1971

The above well was plugged as follows:

922 ft of 8 5/8 surface pipe cemented & circulated. 4778 ft of 5 1/2
long string cemented with 75 sacks. Perf. 4760-66 ft. Sand back
to 4725 ft, 5 sacks cement with bailer. Pulled 3380 ft of 5 1/2. Set
25 ft rock bridge at 325 ft. Fill hole with 5 yds of redimix to
surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Biberstein
Well Plugging Supervisor

DATE 4/15/71
INV. NO. 3555-W