

Form CP-3
Rev. 6-26-62

~~10~~
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Strata Drilling Co. Inc.

Complete Address: Box 355, Great Bend, Kansas

Lease Name Curtis Well No. # 1

Location C SE NW Sec. 26 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 782

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Lost Hole (2nd lost hole on this location)

Plugging Contractor: Strata Drilling Co. Inc.

Address: Box 355, Great Bend, Kansas License No.

Operation Completed: Hour 5:30AM Day 21st Month May Year 1963

The Above well was plugged as follows:

Circulation was lost and pipe was stuck in sand at 782'. Pipe was shot
off at 390', and 4 drill collars, 8 joints pipe was left in hole. Went
in hole as far as possible, to the caved in sand, with 100' of open drill
pipe, cemented there with 50 sacks cement. Made a plug from an empty dope
barrel, filled with cement, and pushed in hole to 35', tied with wires.
Put 35 sacks cement on this plug, to base cellar. Cementing was done by
Sun Cementing Co.

Rig was skidded 990' from east line and 330' from south line.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ardelia Elving
Well Plugging Supervisor

DATE 5/28/63

INV. NO. 9143-W