

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT**RECEIVED**  
STATE CORPORATION COMMISSION

APR 7 1964

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Time Petroleum CompanyComplete Address: 815 Union National Bldg., Wichita, KansasLease Name Curtis "B" Well No. # 1Location C NE NE Sec. 15 Twp. 26 Rge. 15 (E) (W) WCounty Pratt Total Depth 4365Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     Other well as hereafter indicated:     Plugging Contractor: Strata Drilling Inc.Address: 2421 Tenth St., Great Bend, Kansas License No.     Operation Completed: Hour 11:30AM Day 2nd Month April Year 1964

The Above well was plugged as follows:

377' of 8 5/8" surface pipe, cemented with 350 sacks. Fluid level in hole was 250', 1st cementing plug and 1/2 sack hulls was pushed to 370', and cemented with 25 sacks, through the drill pipe. Hole was losing mud and wouldn't stay at a level when filled. Hole was filled full with heavy mud and for 5 hours mud was added to hole before it equalized and the hole held its mud, without loss. 2nd cementing plug and 1/2 sack hulls was pushed in mud to 275', and cemented with 25 sacks, through the drill pipe. Fluid level in hole was now at 38', 3rd cementing plug was set at 40', bridged with hulls, and cemented with 10 sacks to base cellar. Rat & mouse hole bridged and cemented with 4 sacks  
I hereby certify that the above well was plugged as herein stated.

**INVOICED**DATE 4/9/64INV. NO. 8916-12Signed: Archie Elving  
Well Plugging Supervisor