

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name U. S. Hydrocarbon Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Kearns Well No. # 1

Location C SW NW Sec. 12 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling, Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No.

Operation Completed: Hour 3:00PM Day 21st Month April Year 1966

The Above well was plugged as follows:

305' of 8 5/8" surface pipe, cement circulated with 325 sacks. Fluid level in the hole was at 125'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 295', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/26/66
INV. NO. 3103-U