

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
JUN 17 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name H-30 Inc.

Complete Address 200 N Main Wichita, Ks

Lease Name Schriver Well No. 1

Location SW/NE/SW Sec. 28-26 Twp. 26 Rge. 11 (E) (W) W

County Pratt Total Depth 4282

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 15 Month 6 Year 1970

The above well was plugged as follows:

330 ft of 8 5/8 surface pipe circulated. 4450 ft of 5 1/2 long string
cemented with 170 sacks. Top perf. 4266 ft. Sand back to 4250 ft.
5 sacks cement with bailer. Pulled 2018 ft of 5 1/2. Set 10 ft rock
bridge at 300 ft, 25 sacks cement. Mud to 40 ft, 10 ft rock bridge,
10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Biberstein
Well Plugging Supervisor

DATE 6/17/70

INV. NO. 2061-W