

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-151-20,411-00-00 (of this well)

Operator's Full Name Frank J. Black

Complete Address Box 250-McPherson, Ks. 67460

Lease Name Fox Well Well No. 1

Location C E/2 SE NW Sec. 3 Twp. 26S Rge. 13 (E) (W) X

County Pratt Total Depth 4435

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373-Geneseo, Ks. 67444 License No. 711

Operation Completed: Hour 11 Pm. Day 28 Month 7 Year 1980

The above well was plugged as follows:

382' 8 5/8" casing. 4 1/2" casing set at 4434'-Plug back to 4250'-Top
pref., at 4142'-4152'-Sand back to 4100'-Top sand W/4 sax mixed
cement W/dump bailer. Pull 1980' casing-Sun mixed & pumped 8 sax
hulls-25 sax gel-125 sax 50/50 posmix cement W/4% gel & 3% cc to
top of casing. Shut in W/400# pressure.

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor.

INVOICED

DATE 7-1-80

INV. NO. 2732-W