

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION  
**OCT 21 1966**  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name J. Mark Richardson

Complete Address: 502 Union Center Bldg., Wichita, Kansas

Lease Name Woods Well No. # 1

Location C S/2 NW Sec. 2 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4470'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:                                 

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No.                 

Operation Completed: Hour 2:30AM Day 18th Month Oct. Year 1966

The Above well was plugged as follows:

331' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid  
level in the hole was at 120'. 1st cementing plug and 1/4 sack of hulls  
was pushed in fluid to 300', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with  
10 sacks to the base of the cellar. Rat hole bridged and cemented with  
2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 10/21/66

INV. NO. 4145-u