



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 17 1962

12-17-62

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Fred Damme of Red Tiger Co. has this  
 date requested permission to plug the following described well:

Mr. Fred Damme guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Co.

Complete Address: 1016 Union Center Wichita, Kansas.

Lease Name: Petrowsky #1 Well No. #1

Location: NE-SE-NW Sec. 10 Twp. 26 Rge. 12 (E) (W) X

County Pratt County Total Depth 4295; Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Fred Damme was instructed to plug the well as follows:

367' of 8 5/8" surface pipe circulated with cement. hole filled  
to 180' with heavy drill mud, 1 sack hulls, 1st cementing  
plug and 20 sacks cement. hole filled to 40' with heavy drill  
mud, 1 sack hulls and 10 sacks cement to base of cellar.  
Hat hole bridged and 2 sacks cement.

Very truly yours,

Archie Elving  
 Conservation Division Agent