

JP

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 1 1963
 10-1-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Co.

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name: Repp Well No. # 1

Location: SE SW NE Sec. 10 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4310 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Deacon was instructed to plug the well as follows:

344' of 8 5/8" surface pipe, cemented with 200 sacks. 3800' of 5 1/2" long string, cemented with 140 sacks. Plugged back to 3770'. Top perforation 3535'. Sand to 3500', cement with 5 sacks. Fill hole with mud to 300', 10' rock bridge, cement with 20 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent