



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1964
10-12-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Sept 27 - 1964

Dear Sir:

Mr. Hoberecht of Ace Pipe Pulling Co. has this

date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Champlin Oil & Refining Co.

Complete Address: P.O. Box 308 Ellinwood, KANSAS

Lease Name: Miskimen Well No. #2

Location: Sw-Ne-Se= Sec. 32 Twp. 26 Rge. 12 (E) (W) w

County Pratt Total Depth 4298 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hoberecht was instructed to plug the well as follows:

Use 800' of 10 3/4" Surface Pipe cemented with 450 sacks of cement.

4270' of 5 1/2" Long String cemented with 225 sacks cement. Top Perf.

4177 sand to 4160 cemented with 5 sacks; mud to 250 feet. 10 ft Rock

Bridge, 35 sacks cement; mud to 40 feet, 10 feet Rock Bridge, 30 sacks

cement to base of cellar. 2070 feet of 5 1/2" recovered.

Very truly yours,

Herman Justice