



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 25 1963

2-25-63

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Aubrey Richardson of L. B. Jackson Drlg. Co has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: L. B. Jackson Drilling Co.

Complete Address: 503 Mayo Bldg., Tulsa, Oklahoma

Lease Name: DeGolyer Well No. # 1

Location: C SE SE Sec. 2 Twp. 35S Rge. 19 (E) (W) W

County Comanche Total Depth 5718 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

451' of 8 5/8" surface pipe set at 463' derrick floor.

circulated with cement. Fill hole with heavy mud to 240'.

1/2 sack hulls, 1st cementing plug, cement with 20 sacks.

Fill hole with heavy mud to 40', 1/2 sack of hulls, 2nd

cementing plug, cement with 10 sacks to base cellar. Rat

and mouse hole bridged and cemented with 4 sacks.

Very truly yours,

Audie Elving
 Conservation Division Agent