

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name W. L. Kirkman, Inc.

Complete Address Box 18611, Wichita, Ks. 67207

Lease Name Berry Well No. 1

Location NW NE Sec. 32 Twp 26s Rge. 14 (E) (W) X

County Pratt Total Depth 3008

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:15 Am. Day 1 Month 10 Year 1980

The above well was plugged as follows:

779' 8 5/8" casing w/400 sax cement. 4 1/2" casing set at 3008 w/150
sax cement. Top pref's at 2980 to 82'-Sand back to 2850'-Top sand
w/4 sax mixed cement w/dump bailer. Sun mixed & pumped in 8 5/8"
casing 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4% gel
& 3% cc to top of casing. Shut in w/200# pressure.

RECEIVED
STATE CORPORATION COMMISSION
OCT - 6 - 1980
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-10-80
INV. NO. 3299-W