



KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 6 1965  
7-6-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name M. G. Stead Well No. # 1

Location SW SW NE Sec. 27 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4419'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 11:30AM Day 1st Month July Year 1965

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cemented with 300 sacks. 4419' of 5 1/2" long string, cemented with 300 sacks. Top perferation 4328'. Bottom of the hole was sanded to 4300', and cemented with 5 sacks. 3105' of 5 1/2" long string was recovered from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to 300', and 10' of rock bridge on plug. 9 sacks of cement was mixed in barrel, and put on plug at 290', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 16 sacks of cement was addeed to the plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-6-65

INV. NO. 1409-w

Signed: Archie Elving  
Well Plugging Supervisor