

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1965
7-19-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Stead Well No. # 2

Location SW NE NE Sec. 27 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4416'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 12:45PM Day 17th Month July Year 1965

The Above well was plugged as follows:

357' of 8 5/8" surface pipe, cement circulated. 4403' of 5 1/2" long string,
cemented with 250 sacks. All perferation had been squeezed with 75 sacks.
Drilled to an open hole. Bottom of the hole was sanded to 4395', and cem-
ented with 5 sacks. 3168' of 5 1/2" long string was recovered from the hole.
Fluid was up in the hole. Bridge plug was pushed in fluid to 250', and
10' of rock bridge, on plug at 250'. 6 sacks of cement was mixed in barrel
and put on plug at 240', through the dump bailer. And let set over-night.
Next morning hole was bailed dry, and 19 sacks of cement was added to the
plug. Hole was filled with mud to 40', and 10' of rock bridge, and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/20/65

INV. NO. 1484-W

Signed: Archie Elving
Well Plugging Supervisor