

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

APR 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Continental Oil Company

Complete Address: Box 267, Great Bend, Kansas

Lease Name James R. Cooper Well No. # 1

Location NE NE SW Sec. 27 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4370

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Western Petroleum Co., Inc.

Address: 925 Patton, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00PM Day 14th Month April Year 1964

The Above well was plugged as follows:

367' of 8 5/8" surface pipe, cemented with 200 sacks. Drilling mud  
in pits was pumped into hole. 1st cementing plug and 1/2 sack hulls  
was pushed through fluid to 300', and cemented with 25 sacks, through  
the drill pipe. Fluid in hole was now at 35', 2nd cementing plug,  
bridged with hulls at 35', and cemented with 10 sacks to base cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/16/64

INV. NO. 8492-W