


DISTRICT CONSERVATION AGENT'S REPORT



To

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

File No. _____

Location SENE

Sec. 20 Twp. 26 Rge. 12W

I have today completed supervision of plugging of:

Well No. 1 Lease Home

Operator Helmreich Payne Address _____

Field _____ County Pratt

Total Depth 4417 Feet.

(Describe briefly the manner in which the well was plugged)

Hole filled with heavy rotary mud from 4417 to 448 ft
and hole bridged at 448 ft and a 15 ft cement plug set in
bridge and a cement plug set in top of surface pipe
at bottom of well.

20T. 26 12W
AGE-2-11 34

G. T. Alexander
District Conservation Agent


Date 1-5-38

HOTEL CALBECK

Coffee Shop

Pratt, Kansas

Log of Haeme No 1



| | | | |
|------|---|------|---------------------|
| 0 | - | 190 | Sand |
| 190 | - | 300 | Red Bed |
| 300 | - | 420 | Sand |
| 420 | - | 550 | Red Bed |
| 550 | - | 725 | Red Bed |
| 725 | - | 780 | Anhydrite |
| 780 | - | 830 | Shale |
| 830 | - | 960 | Red Bed |
| 960 | - | 990 | Shale |
| 990 | - | 1010 | Red Bed |
| 1010 | - | 1070 | Shale + Shale |
| 1070 | - | 1295 | Sandy Shale |
| 1295 | - | 1435 | Shale |
| 1435 | - | 1525 | Shale |
| 1525 | - | 1540 | Lime |
| 1540 | - | 1735 | Shale + Broken Lime |
| 1735 | - | 2060 | Lime |
| 2060 | - | 2150 | Shale |
| 2150 | - | 2265 | Sandy Lime |
| 2265 | - | 2645 | Shale + Lime Shells |
| 2645 | - | 2940 | Shale |
| 2940 | - | 3720 | Broken Lime + Shale |
| 3720 | - | 4085 | Lime - Kansas City |
| 4085 | - | 4135 | Chert + Lime |
| 4135 | - | 4343 | Lime + Chert |
| 4343 | - | 4427 | Jimpson Sand |
| 4427 | - | 4470 | Delicious Lime |

PLUGGING
 FILE SEC 20 T26 R12 E
 BOOK PAGE 2 LINE 34