

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-10-72  
JAN 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Robert L. Austin

Complete Address Box 169 Stafford, Ks

Lease Name Hoeme Well No. 6

Location SW/NE/SW Sec. 20 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4521

Abandoned Oil Well        Gas Well        Input Well        SWD Well X D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 1:00 PM Day 6 Month 1 Year 1972

The above well was plugged as follows:

263 ft 8 5/8 surface pipe cemented with 250 sacks. 4471 ft 5 1/2 long

string cemented with 150 sacks. Open hole. Sand back to 4460 ft,

5 sacks cement with bailer. Pulled 2332 ft 5 1/2. Pump 2 sacks hulls,

15 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell B. Hunter  
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4989-W