

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 8 1966

12-8-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name R. W. Rine Drilling Company

Complete Address: 600 Garvey Bldg., Wichita, Kansas

Lease Name Hoeme Gas Unit Well No. # 1

Location NE SW SE Sec. 20 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 4330'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:45AM Day 7th Month Dec. Year 1966

The Above well was plugged as follows:

440' of 8 5/8" surface pipe, cement circulated. 4330' of 5 1/2" long string,  
cemented with the top of the cement at 1875'. Plug back T. D. 2440'. Top  
perferation 2384'. All perferations were squeezed with 80 sacks of cement,  
bringing the top of the cement to 1800' in the 5 1/2" casing. 1760' of 5 1/2"  
long string was recovered from the hole. Bridge plug was pushed in fluid  
to 300', rock bridge from 300' to 290'. 10 sacks of cement was mixed in  
barrel, and put on plug at 290', through the dump bailer, and let set  
over-night. Next day hole was bailed dry, and 15 sacks of cement was added  
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30',  
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/9/66  
INV. NO. 4422-01