

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1967
7-28-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed July 11, 1967.

Operator's Full Name Murfin Drilling Company & Home-Stake

Complete Address 617 Union Center Bldg., Wichita, Kansas 67202

Lease Name Stalcup Well No. # 1

Location SW NE SW Sec. 11 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 4325'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company

Address 617 Union Center Bldg., Wichita, Ks. License No.

Operation Completed: Hour 12:30 P.M. Day 25th Month July Year 1967

The above well was plugged as follows:

365' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level in the hole was at 125'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 300', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',
and cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Ewing
Well Plugging Supervisor

DATE 7/28/67

INV. NO. 6036-w