

15-151-10945-00-01

Form CP-3
Rev. 6-26-62

R KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1965
3-24-65
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Hinkle Oil Company

Complete Address: 1016 Union Center, Wichita, Kansas

Lease Name Stalcup Well No. # 1

Location NW NW SW Sec. 11 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 4306'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00AM Day 22nd Month March Year 1965

The Above well was plugged as follows:

342' of 8 5/8" surface pipe, cemented with 250 sacks. 3804' of 4 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the hole
was sanded to 3800', and cemented with 3 sacks. 3000' of 4 1/2" long string
was recovered from the hole. Fluid level in the hole was at 40'. Bridge
plug was pushed in fluid to 275', and 10' of rock bridge on plug. 5 sacks
of cement was mixed in barrel, and put on plug at 265', through the dump
bailer, and let set over-night. Next morning hole was bailed dry, and 20
sacks of cement was added to the plug. Hole was filled with mud to 40',
and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/24/65

INV. NO. 868-W