

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 1 1966
7-1-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Lyons Pipe & Supply

Complete Address: Box 581, Lyons, Kansas

Lease Name Petrowsky "A" Well No. # 2

Location SW NE SW Sec. 30 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4319'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 5:15PM Day 28th Month June Year 1966

The Above well was plugged as follows:

811' of 8 5/8" surface pipe, cemented with 400 sacks. 4281' of 4 1/2" long
string, cemented with 900 sacks. Plug back T. D. 3875'. Top perforation 3765'
Bottom of the hole was sanded to 3750', and cemented with 3 sacks, through
the dump bailer. 1024' of 4 1/2" long string was recovered from the hole. Bridge
plug was pushed in fluid to 350', rock and sand bridge from 350' to 330'. 5
sacks of cement was mixed in a barrel, and put on plug at 330', through the
dump bailer, and let set over-night. Next day hole was bailed dry, and 20
sacks of cement was added to the plug. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/1/66
INV. NO. 3490-U