

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 147-13 County: Pratt

Location: SW SE SE Sec. 30 Twp. 26 Rge. 12 (E) (W) X

Name of Field: _____ Total Depth: 4316

I have this date completed supervision of plugging of:

Lease Name: Sitmer Well No. 1

Operator's Full Name: Great Bend Pipe & Supply

Complete Address: Great Bend, Kans.

Plugging Contractor: Southwest Pipe Pulling Co.

Address: Great Bend, Kans. License No. _____

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 10:10 PM Day 7 Month December Year 1958

The above well was plugged as follows:

835' of 8 5/8" surface casing circulated with cement. Top Perf 364'-365'. Sand hole to
3500' and dump 5 sack cement top sand with dump bailer. Heavy mud to 300'. Rock bridge
10' from 300 to 290'. 20 sack cement placed from 290 to 250'. Heavy mud to 40 with a 10'
rock bridge to 30'. Cement from 30' to base of cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 30 T.26 R.12W
BOOK PAGE 147 LINE 13