

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSIONJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasAPR 2 1965  
4-2-65  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Lyons Pipe & Supply CompanyComplete Address: Box 581, Lyons, KansasLease Name R. Petrowsky Well No. # A-1Location N/2 SW Sec. 30 Twp. 26 Rge. 12 (E) (W)WCounty Pratt Total Depth 4306'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Lynch Casing Pulling CompanyAddress: Route 4, Great Bend, Kansas License No. 457Operation Completed: Hour 3:00PM Day 31st Month March Year 1965

The Above well was plugged as follows:

810' of 8 5/8" surface pipe, cemented with 400 sacks. 4282' of 4 1/2"  
long string, cemented with 633 sacks. This is an open hole. Bottom  
of the hole was sanded to 4275', and cemented with 3 sacks. 1533' of  
4 1/2" long string was recovered from the hole. Fluid in the hole was  
bailed down to 300', bridge plug was set on fluid at 300', and 10'  
of rock bridge, and cemented with 25 sacks. Hole was filled with mud  
to 40', and 10' of rock bridge, and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 4/2/65INV. NO. 919-W