

15-151-10641-0000

Form CP-3
Rev. 6-26-62

VP
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1966
3-18-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name High Plains Production Company

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name M. Schwertfeger Well No. # 2

Location SW SE SW Sec. 30 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4311'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractors: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 9:00AM Day 14th Month March Year 1966

The Above well was plugged as follows:

819' of 8 5/8" surface pipe, cement circulated. 4294' of 4 1/2" long string,
cemented with 400 sacks. Bottom of the hole was sanded to 4100', and cem-
ented with 3 sacks, through the dump bailer. 1225' of 4 1/2" long string was
recovered from the hole. Fluid in the hole was bailed down to 300', rock
bridge from 300' to 290', and cemented with 4 yards of ready-mix cement
from 290' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/18/66
INV. NO. 2888-4

Signed: Aubie Elving
Well Plugging Supervisor