

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1966
3-21-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name High Plains Production Company

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name M. Schwertfegers Well No. # 1

Location SW SW SW Sec. 30 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 4295'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No.

Operation Completed: Hour 11:00AM Day 19th Month March Year 1966

The Above well was plugged as follows:

908' of 8 5/8" surface pipe, cement circulated. 4295' of 4 1/2" long string,
cemented with 400 sacks. Top perforation 4251'. Bottom of the hole was
sanded to 4100', and cemented with 3 sacks. 1460' of 4 1/2" long string
was recovered from the hole. Fluid in the hole was bailed down to 300',
bridge plug and rock bridge from 300' to 280', hole was filled with 4
yards of ready-mix cement from 280' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/21/66
INV. NO. 2900-W