

~~10~~ KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1964
12-21-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name McAdams Pipe & Supply Company

Complete Address: 2700 North Main St., Great Bend, Kansas

Lease Name Petrosky "B" Well No. # 2

Location SW NW SE Sec. 30 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4316

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 5:30PM Day 20th Month Dec. Year 1964

The Above well was plugged as follows:

828' of 8 5/8" surface pipe, cemented with 400 sacks. 4288' of 4 1/2" long
string, cemented with 1000 sacks (tried to circulate). Bottom of the
hole was sanded to 4270', and cemented with 3 sacks. Fluid in the hole
was bailed down to 280'. Bridge plug was set on fluid at 280', and 10'
of rock bridge, and cemented with 25 sacks. Hole was filled with mud to
40', and 10' of rock bridge, and cemented with 10 sacks to the base of
the cellar.

1537' of 4 1/2" long string was recovered from the hole.

I hereby certify that ~~the above well~~ **NOVED** was plugged as herein stated.

DATE 12/21/64

INV. NO. 370-W

Signed: Archie Elving
Well Plugging Supervisor