

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,278-00-00
NW, Sec. 9, T 26 S, R 11 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name McOster Well # 1

Operator: J. A. Allison
Name & 300 West Douglas, Suite 305
Address Wichita, KS 67202

County Pratt

Well Total Depth 4437 feet 144.20

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 26 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Norman Voth

(company name) Kelso Casing Pilling (phone) 316-938-2428

were: 5 1/2 set at 4147 PBD 4118. Perfs 4045 to 61. Pumped 40 sx cement on
bottom. Stopped plug at 3900' - pumped 25 sx gel and 25 sx weight mud in Annus.
Recovered 3200 of 5 1/2. Squeezed well with 3 sx hulls, 20 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, and released 8 5/8 plug followed by 125 sx cement.

Signed J. A. Allison
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 26 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4147 PBD 4118. Perfs 4045 to 61. Pumped 40
sx cement on bottom. Stopped plug at 3900' - pumped 25 sx gel and 25 sx weight
mud in Annus. Recovered 3200 of 5 1/2. Squeezed well with 3sx hulls, 20 sx gel,
50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" plug followed by 125
sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Allied

RECEIVED
STATE CORPORATION COMMISSION
FEB 02 1984
Conservation Division
Wichita, Kansas

I hereby certify that the above plugging instructions were given as here stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 2-3-84
INV. NO. 0035

Signed J. A. Allison
(TECHNICIAN)