

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,213-00-00

NE NW SE, Sec. 9, T 26 S, R 11 W/E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Stambaugh Well # 1

Operator: J. A. Allison  
Name & 300 West Douglas, Suite 305  
Address Wichita, KS 67202

County Pratt

Well Total Depth 4120 feet 133.90

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 22 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelso and James Ray

(company name) Kelso (phone) 316-938-2457

were: 5 1/2 set at 4104 Perfs 4054-64 4056-64

1st plug pumped 40 sx cement on bottom and plug stopped at 3400'

2nd plug squeezed through head with 1 sack hulls, 20 sx gel,

8 5/8" had a hole and gel circulated in cellar. Ran 600' of 2" tubing and spotted

100 sx cement at 600'. Pulled tubing to 300' and circulated 65 sx cement to surface.

Signed J. A. Allison  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 pm Day: 24 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4104 Perfs 4054-64 4056-64

1st plug pumped 40 sx cement on bottom and plug stopped at 3400'

2nd plug squeezed through head with 1 sack hulls and 20 sx gel.

8 5/8" had a hole and gel circulated in cellar. Ran 600' of 2" tubing and spotted

100 sx cement at 600'. Pulled tubing to 300' and circulated 65 sx cement to surface.

Remarks: Use 50/50 Pozmix 6% gel. They recovered 3050 5 1/2" casing.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / ~~did not~~) observe this plugging.

Signed J. A. Allison  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED

DATE 3-5-84

INV. NO. 0521