

To: 1 040848
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-27

API NUMBER 15- 151-22,062 - 00-00
SE SW NW, SEC. 17, T 26 S, R 11 X/X
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name:
Address P.O. Box 48788
Wichita, KS 67201

Lease Name Gythiel Well # 1
County Pratt
Well Total Depth 4220 137.15 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 230

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 27 Month: 5 Year: 19 94

Plugging proposal received from Vernon Duntz Jr.
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4213' w/175 sx cement, Perfs at 4098-4116'
1st plug sand back to 4040' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 9:45 a.m. Day: 27 Month: 5 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by United. Recovered 2600' of 5 1/2" casing. Wichita, Kansas
(if additional description is necessary, use BACK of this form)

INVOICED
observe this plugging.

DATE 6-7-94
INV. NO. 40545

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 03 1994
CONSERVATION DIVISION
Wichita, Kansas