

To: 1 090012  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,008 - 66-60  
SE NE SW, SEC. 18, T 26 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3180  
Operator: Deutsch Oil Company  
Name:  
Address 107 N. Market, Suite 1115  
Wichita, KS 67202

1650 feet from S section line  
2970 feet from E section line  
Lease Name Fisher Well # 1-18  
County Pratt 139.75  
Well Total Depth 4300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929  
Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from John Armbruster  
(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 520'  
1st plug at 600' with 50 sx cement, 2nd plug at 290' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:15 p.m. Day: 10 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,  
2nd plug at 290' with 50 sx cement,  
3rd plug at 40' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (PRINTED) did not observe this plugging.

Signed [Signature]  
(TECHNICIAN)

DATE 10-18-90

INV. NO. 29653