

9-18-87

To: 1,070421  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,849-00-00

SE SW SW, SEC. 18, T 26 S, R 11 W/X

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7543

Lease Name Fisher Well # 1-18

Operator: Woods Petroleum Corporation

County Pratt 139.75

Name & Address P.O. Box 947

Well Total Depth 4300 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling Inc. License Number 5380

Address Box 8609, Wichita, KS 67208

Company to plug at: Hour: 4 a.m. Day: 18 Month: 9 Year: 19 87

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1857'

Anhydrite 650-70'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at base of surface pipe plus 30' with 40 sx cement, 3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7 a.m. Day: 18 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 670' with 50 sx cement,

2nd plug at 270' with 40 sx cement,

3rd plug at 40' with 10 sx cement.

4th plug to circulate rathole with 10 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE 9-24-87

INV. NO. 18237