

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰¹ 15-151-21864-00-00
Spot: CS2SEW Sec/Twnshp/Rge: 5-26S-14W
2970 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: ELLIS Well Number: 1
County: PRATT Total Vertical Depth: 4420 feet

Operator License No.: 5010 Conductor Pipe: Size _____ feet:
Operator Name: KNIGHTON OIL COMPANY, INC. Surface Casing: Size 8.625 feet: 263 WITH 265 SX CMT
Address: 710 PETROLEUM BUILDING Production: Size 5.5 feet: 4398 WITH 215 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____ 143.65

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2000 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CARL GILPIN Company: KNIGHTON OIL Phone: (316) 264-7918

Proposed Plugging Method: PUMP 300# HULLS DOWN 5 1/2" CASING AND FILL WITH CMT. USE 100 SX CMT FOR BACK.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/06/2000 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3914-19'. SQUEEZED AT 550-540'. PUMPED DOWN 5 1/2" WITH 400# HULLS & 300 SX CMT. MAXIMUM PRESSURE 700 PSIG. SHUT IN PRESSURE 250 PSIG. PUMPED DOWN 8 5/8" X 5 1/2" ANNULAS WITH 100 SX CMT. MAXIMUM PRESSURE 200 PSIG. SHUT IN PRESSURE 50 PSIG.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 2000

Remarks: USED 65/35 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 01

Signed Richard W. Lacey

(TECHNICIAN)
DEC 08 2000

INVOICED
DATE 12/12/00
NO. 2001061116

MP

[Signature]
Form CP-2/3