

1080164

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,808-00-00

W/2 NW NW, SEC. 7, T 26 S, R 14 (W/2)

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Abrams Well # 1

Operator: Kelso Casing Pulling

County Pratt

Name & Address Box 347

Well Total Depth 4300 139.75 feet

Chase, KS 67524

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 11 Month: June Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4300' Perfs 4041-44' 3641-44' PBD 4300 Insert

1st plug sand back to 3775 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and pump an additional 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 29 1984

Plugging Proposal Received by *J. A. [Signature]* (TECHNICIAN)

Persons attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:40 am Day: 11 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4300' Perfs 4041-44' 3641-44' PBD 4300 Insert

1st plug sanded back to 3775' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 500# and shut in pressure 100#

Remarks: They recovered 2300' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(if applicable) observe this plugging.

DATE 7-2-84

Signed *J. A. [Signature]* (TECHNICIAN)

INV. NO. 2228