

To: 1020206
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-31
-00-0260 R
API NUMBER 15- 151-20,116-A
C NW NE, SEC. 12, T 26 S, R 14 W/EX
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408
Operator: Trans Pacific Oil Corporation
Name & Address: 410 One Main Place
Wichita, KS 67202

Lease Name Slicker "OWWO" Well # 1
County Pratt 146.90
Well Total Depth 4520 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Trans Pac Drilling, Inc. License Number 5841
Address 410 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 31 Month: 1 Year: 19 89

Plugging proposal received from Gary Pugh
(company name) Trans Pac Drilling, Inc. (phone) 316-262-3596

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 852-882'
1st plug at 4520' with 25 sx cement, 2nd plug at 880' with 50 sx cement,
3rd plug at 320' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 a.m. Day: 31 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 4520' with 25 sx cement,
2nd plug at 880' with 50 sx cement,
3rd plug at 320' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (check) or (not) observe this plugging.

DATE 2-7-89
INV. NO. 23884
1-31

Signed John R. Barlow (TECHNICIAN)