

1 010157

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,265-00-00  
C SE SE, SEC. 12, T 26 S, R 14 W/S  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
Operator: Kelso Casing Pulling, Inc. purchased from:  
Name & Retro Kansas Oil Producers, Inc.  
Address 107 Country Side Office Park  
9415 East Harry  
Wichita, KS 67207

Lease Name Bales Acres, Inc. # 1  
County Pratt 144.63  
Well Total Depth 4450 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:10 am Day: 12 Month: August Year: 1986

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) (316) 938-2457

were: 1st plug sand back to 3800' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze 3sx hulls and 2 sx hulls mixed in with 120 sx cement through the  
8 5/8" surface pipe.

4 1/2" at 4450' PBTD at 3905' Perfs at 4069-4297'

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:35 am Day: 12 Month: August Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 3800' and dumped 4 sx cement  
on top of sand through bailer, and 2nd plug squeezed 3 sx hulls mixed with water  
and 2 sx hulls mixed in 120 sx of ATL through 8 5/8" surface pipe.

Maximum pressure 250 psi and shut in 0 psi.

Remarks: Recovered 2800' of 4 1/2" casing. Used ATL -- Allied's Lite --- pumped by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(copy to ~~XXXXXX~~) observe this plugging.

DATE AUG 1 8 1986

Signed Joel D. DeLoe  
(TECHNICIAN)

INV. NO. 14754

AUG 1 5 1986