

To: 1041276
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-17

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Operator: Bowers Drilling Company, Inc.

Name:

Address 125 N. Market, Ste. 1425

Wichita, KS 67202

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SMO Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 2:45 p.m. Day: 17 Month: 11 Year: 19 97

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Co., Inc. (phone) 316-886-5520

was: 5 1/2" at 4450' w/150 sx cement, PBTD 4263', Perfs at 3750' & 4269'

1st plug set CIBP at 3720' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3:30 p.m. Day: 17 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3710' and dumped 2 sx cement on top of plug
through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2080' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 11-24-97

INV. NO. 49583

Signed Stephen J. Pfeifer
(TECHNICIAN)