

2-9

Docket #E-23,542

API NUMBER 15-151-20,799-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1989
CONSERVATION DIVISION
Wichita, Kansas

NW NW NW, SEC. 13, T 26 S, R 14 W 1/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.
Name & Address: P.O. Box 48788
Wichita, KS 67201

4950 feet from S section line

4950 feet from E section line

Lease Name Neelly Well # 1

County Pratt 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 9 Month: 2 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4399' PBTD 4359' Perfs at 4311-4316' Elevation 1968' GL

1st plug sand back to 4260' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 a.m. Day: 9 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 250 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2137' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 2-17-89

INV. NO. 23966

Signed Stephen J. Pfeifer (TECHNICIAN)

Electra Log Inc.

SEC. 13 TWP. 26^s RGE. 19^w

Correlation Log

COMPANY Raymond Oil Co

WELL # 1 Noelly

FIELD _____

COUNTY Pratt STATE Ks.

Location

Sec. 13 Twp. 26^s Rge. 19^w

Other Services:

cement top 10

Permanent Datum: Ground level, Elev. 1968

Log Measured From K.B. 9 Ft. Above Perm. Datum

Drilling Measured From Kelly Bushing

Elev.: K.B. 1977

D.F. 1975

G.L. 1968

Date	9-23-80	9-23-80		
Run No.	1	2		
Depth - Driller				
Depth - Logger	4359	4359		
Btm. Log Inter.	4358	4346		
Top Log Inter.	2700	2700		
Casing - Driller	5 1/2 @	5 1/2 @	@	@
Casing - Logger				
Bit Size				
Type Fluid in Hole	water	water		
Dens.				
Visc.				
pH				
Fluid Loss				
Source of Sample				
Rm @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Source: Rmf				
Rmc				
Rm @ BHT	@ °F	@ °F	@ °F	@ °F
Time Since Circ.				
Max. Rec. Temp.	°F	°F	°F	°F
Equip.	135	135		
Location				
Recorded By	K-Frenzel	K-Frenzel		
Witnessed By	Art Schoenhafner			

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1980
CONSERVATION DIVISION
Wichita, Kansas