

10-28

1 080037

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,684-00-00

NW NE, SEC. 23, T 26 S, R 14 W/E

4620 feet from S section line

1980 feet from E section line

Lease Name Hensley Well # 1

County Pratt 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

TECHNICIAN'S PLUGGING REPORT

Operator License # 3738

Operator: Sunrise Oilfield Supply

Name & Address 621 17th Street, Suite 845

Denver, CO 80293

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor, Great Bend Casing Pullers Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:50 a.m. Day: 28 Month: 10 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4404' PBD 4359' Perfs at 4370-72, 4326-32, 4000-4005'

1st plug sand back to 3950' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1988

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 28 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 130 sx cement.

Maximum pressure 250 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3009' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 11-3-88

Signed Mike Luthi (TECHNICIAN)

INV. NO. 22871 10-28

DEC 9 1988

JAN 25 1989