

1052382

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151,20,777-00-00
C NW SE SEC. 23, T 26 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BERRY WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT

144.95

OPERATOR LICENSE # 5893

WELL TOTAL DEPTH 4460 FEET

OPERATOR: PRATT WELL SERVICE INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4454' WITH 100SX

NAME AND PO BOX 847

SURFACE CASING: SIZE 8 5/8" @ 352' WITH 300 SX

ADDRESS PRATT, KS 67124-0847

RECEIVED
STATE CORPORATION COMMISSION

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL APR 17 2000 D/A

OTHER WELL AS HEREINAFTER INDICATED _____ CONSERVATION DIVISION, Wichita, Kansas

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 10 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM AARON HAMMERSCHMIDT

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-2531

WERE: PERFS AT 4396-4401

SET CIBP @ 4350' AND 2 SX CEMENT. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX

CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG - 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 10 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SET CIBP @ 4350' AND 2 SX CEMENT. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX

CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG - 100 SX CEMENT. MAXIMUM PRESSURE AT 200 PSIG.

SHUT IN PRESSURE AT 0 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 910' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 4/20/00 SIGNED Richard M. Lacey
(TECHNICIAN)

TEL NO. 066621

FORM CP-2/3

Handwritten initials and a large circled 'R'.