

1 030945

5-13-88

API NUMBER 15-151-00365 - 80-03

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NE, SEC. 24, T 26 S, R 14 W/R
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3181

Lease Name Fincham Well # 1

Operator: W.K. Black P.P.P.L.P.
Name & Address 1540 North Broadway, Suite 202
Wichita, KS 67214

County Pratt 146.25
Well Total Depth 4500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 882

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 13 Month: 5 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4486' Perfs at 4288-98' Elevation 1965' GL

1st plug pump 2 sx hulls and 25 sx Class H cement to bottom,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 140 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 13 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx Class H cement to bottom,
2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 140 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2047' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (void) observe this plugging.

DATE 5-19-88

Signed Steve Luthi (TECHNICIAN)

INV. NO. 20766
5-13

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1988
CONSERVATION DIVISION
Wichita, Kansas

15-151-00365-00-03

Marked

Electra Log Inc.

Sec. 24 Twp. 26S Rge. 14W
 Radiation Log
 Sonic Cement
 Bond Log

W. K. BLACK, INC.
 P. O. BOX 801
 PRATT, KANSAS 67124
 316-672-5712

COMPANY KANSAS CRUDE
W. K. BLACK, INC.
 WELL FINCHAM #1 P. O. BOX 801
 FIELD _____ PRATT, KANSAS 67124
 COUNTY PRATT STATE KANSAS
 316-672-5712

Location C NW SE NE Other Services: _____
 Sec. 24 Twp. 26S Rge. 14W

Permanent Datum: GROUND LEVEL Elev. 1965'
 Log Measured From K.B. FIVE Ft. Above Perm. Datum
 Drilling Measured From KELLY BUSHING
 Elev. K.B. 1970'
D.F. 1967'
G.L. 1965'

Date	4-21-81	SONIC BOND		
Run No.	ONE	TWO		
Depth - Driller	4458'	4458'		
Depth - Logger	4456'	4456'		
Btm. Log Inter.	4455'	4453'		
Top Log Inter.	3450'	3600'		
Casing - Driller	4 1/2 @	4 1/2 @	@	@
Casing - Logger				
Bit Size				
Type Fluid in Hole	WATER	WATER		
Dens.				
Visc.				
pH				
Fluid Loss		ml	ml	ml
Source of Sample				
Rm @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F
Source: Rmf Rmc				
Rm @ BHT	@ °F	@ °F	@ °F	@ °F
Time Since Circ.				
Max. Rec. Temp.	°F	°F	°F	°F
Equip.	137 KANSAS	137 KANSAS		
Location				
Recorded By	B. STUCKY	B. STUCKY		
Witnessed By				