

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,879-00-66
C NE NW, Sec. 26, T 26 S, R 14 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8295

Lease Name Hemphill Well # 1

Operator: William C. Lake
Name & P. O. Box 386
Address Derby, KS 67037

County Pratt

Well Total Depth 4522 feet 146.97

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 379

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 7:00 am Day: 18 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO John Luther

(company name) Pratt Well Service (phone) 1-800-362-0597
316-672-2531

were: 4 1/2 set at 4519 Perfs 3461-64

1st plug sand back to 3360' and dump 4 sx cement through the bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump 100 sx cement.

Maximum pressure 350# and shut in pressure 100#

Signed J. H. Mueg
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:20 am Day: 18 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4519 Perfs 3461 - 64

1st plug sanded back to 3360' and dumped 4 sx cement through the bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 350# and shut in pressure 100#

Remarks: They recovered 3100' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Halliburton

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed J. H. Mueg
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 5-1-84

INV. NO. 1317