

1 050692

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,684-00-00

NW NENW, SEC. 22, T 26 S, R 14 W/E
4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Lundgrin Well # "A" #1

Operator: F & M Oil Co. Inc
Name &

County Pratt 152.60

Address 422 Union Center
Wichita Kansas

Well Total Depth 4360' "Viola" feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 360'

67202

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co, Inc License Number 5103

Address Wichita K-422 Union Center-Wichita-Kansas 67202

Company to plug at: Hour: 8:00am Day: 22 Month: November Year: 19 85

Plugging proposal received from Lyle Casson

(company name) Union Drilling Co. Inc (phone) 316-262-2636

were: To keep hole full of heavy mud & spot cement
plugs through drill pipe. 1st plug @ the base of
the anhydrite w/50sx, 2nd plug @ 400' w/50sx
3rd plug @ 40' w/solid bridge plug + 10sx
Circulate Rathole w/50sx

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15am Day: 22 Month: November Year: 19 85

ACTUAL PLUGGING REPORT Kept hole full of heavy mud & spot cement
plugs through drill pipe. 1st plug @ 913' w/50sx
2nd plug @ 400' w/50sx, 3rd plug @ 40' w/solid
Bridge Plug. Circulated 10sx of cement in the
rathole

Remarks: Halliburton pumped 60/40 po2 mix 6% gel cement
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-5-85

INV. NO. 11263

11-22

STATE CORPORATION COMMISSION
RECEIVED

NOV 25 1985

Signed Richard W. Lacey
(TECHNICIAN)