

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20767-00-00
Spot: CSWSESE Sec/Twnshp/Rge: 32-26S-14W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: BERRY Well Number: 1
County: PRATT Total Vertical Depth: 4623 feet

Operator License No.: 31142 Conductor Pipe: Size _____ feet:
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 8.625 feet: 287 \$150.25
Address: 155 N. MARKET, STE 1010 Production: Size 5.5 feet: 4205 WITH 250 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2001 8:45 AM
Plug Co. License No.: 31142 Plug Co. Name: PETROLEUM PROPERTY SERVICES, INC.
Proposal Rcvd. from: LARRY WALLERT Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1558

Proposed Plugging Method: SAND TO 3420' & 5 SX CMT ON TOP. 1ST PLUG AT 950' WITH 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/11/2001 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4105'. PERFS AT 3486-89' & 4041-44'. SANDED BACK TO 3415' AND PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2' CASING. 1ST PLUG AT 950' WITH 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 6-18-01
WEL NO. 2001061956

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 18 2001
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2030' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

Stephen J. Taylor
(TECHNICIAN)

JUN 14 2001

Form C-2/3 *[Signature]*

MP

ALLIED CEMENTING CO., INC.

8U43

Federal Tax I.D.# 48-0727860

15-151-90767-00-60

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Grant Bond

DATE <u>6-11-01</u>	SEC. <u>32</u>	TWP. <u>26</u>	RANGE <u>14</u>	CALLED OUT <u>6:00 AM</u>	ON LOCATION <u>8:05 AM</u>	JOB START <u>8:30 AM</u>	JOB FINISH <u>10:15 AM</u>
LEASE <u>Berry</u>		WELL # <u>1</u>	LOCATION <u>Byers South 1/4 W N into</u>		COUNTY <u>Pratt</u>	STATE <u>Kansas</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Quality Well Service
 TYPE OF JOB Plug while pulling
 HOLE SIZE 5 1/2" T.D. 4205'
 CASING SIZE 5 1/2" DEPTH 950'
 TUBING SIZE 3 1/2" DEPTH 287'
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS. 4623' PSTD
 DISPLACEMENT

OWNER PPSI
 CEMENT
 AMOUNT ORDERED 110 ex 60/40 poz 6% GEL, 15 ex GEL on side

COMMON	<u>66</u>	@	<u>6.65</u>	<u>438.90</u>
POZMIX	<u>44</u>	@	<u>3.55</u>	<u>156.20</u>
GEL	<u>21</u>	@	<u>10.00</u>	<u>210.00</u>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>1.31</u>	@	<u>1.10</u>	<u>144.10</u>
MILEAGE	<u>15</u>	@	<u>7.00</u>	<u>105.00</u>
TOTAL				<u>\$1049.20</u>

EQUIPMENT

UB
 PUMP TRUCK CEMENTER Steve Stanley
 # 120 HELPER Steve Stanley
 BULK TRUCK
 # 342 DRIVER Lennie Marquis
 BULK TRUCK
 # DRIVER

REMARKS:

1st 950' - 13 ex gel, 50 ex cement, 3 ex gel
2nd 310' - 50 ex
3rd 40' - 10 ex & circulate to surface

SERVICE

DEPTH OF JOB	<u>950'</u>			
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>15</u>	@	<u>3.00</u>	<u>45.00</u>
PLUG		@		
		@		
		@		
TOTAL				<u>\$520.00</u>

CHARGE TO: Petroleum Properties Service
 STREET 155 North Market
 CITY Wichita STATE Kansas ZIP 67202

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

Witnessed by KCC - Steve Pfeifer