

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20705-00-01
Spot: SWSESW Sec/Twnshp/Rge: 33-26S-14W
330 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: MCMANNIS Well Number: 1
County: PRATT Total Vertical Depth: 4148 feet

Operator License No.: 31142 Conductor Pipe: Size _____ feet:
Op Name: PETROLEUM PROPERTY SERVICES, INC Surface Casing: Size 8.625 feet: 304 WITH 230 SX CMT
Address: 155 N. MARKET, STE 1010 Production: Size 4.5 feet: 4144 WITH 250 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____ 34.81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/12/2001 1:45 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: LARRY WALLERT Company: PETROLEUM PROPERTY SERVICE Phone: (316) 265-3351

Proposed Plugging Method: SAND BACK TO 3440' WITH 4 SX CMT. 1ST PLUG AT 950' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/12/2001 3:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:
PBTD 4104'. PERFS AT 3932-36 & 3494-97'. SANDED BACK TO 3436' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2' CASING. 1ST PLUG AT 950' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 6-18-01
INV. NO. 2001061958
RECEIVED
KANSAS CORPORATION COMMISSION
JUN 18 2001
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2229' OF 4 1/2" CASING.
Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)
Form CP-273
JUN 14 2001
MP