

To: 1 090205
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-24

API NUMBER 15- 151-21,600-~~0000~~ 200R
NE NW NE, SEC. 27, T. 26 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30116
Operator: Steve Jones
Name & Address: 112 N. Gray
St. John, KS 67576

4950 feet from S section line
1650 feet from E section line
Lease Name Strong Well # A 1
County Pratt
Well Total Depth 4410 143.32 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor VAL Energy, Inc. License Number 5822

Address Box 322, Haysville, KS 67060

Company to plug at: Hour: 10:30 a.m. Day: 24 Month: 7 Year: 19 92

Plugging proposal received from Jeff Ford

(company name) VAL Energy, Inc. (phone) 316-522-1560

were: 5 1/2" at 4409' w/150 sx cement, PBTB 4367', Perfs at 4298-4302, 4012, 4014, 3944-47'
1st plug sand back 50' above perfs and dump 5 sx cement on top,

2nd plug pump 50 sx cement at 650',

3rd plug pump 50. sx cement at 470',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 24 Month: 7 Year: 19 92.

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 5 sx cement on top of sand through bailer, plugged well through casing,

2nd plug pulled to 650' and spotted 50 sx cement,

3rd plug pulled to 470' and spotted 50 sx cement,

4th plug pulled to 40' nad circulated cement to pit.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing. (STATE CORPORATION COMMISSION)

INVOICED
observe this plugging.

DATE 8-4-92
INV. NO. 35851

RECEIVED
JUL 29 1992
7-29-92
Signed _____ (TECHNICIAN)
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS