

To: **1 040885**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

**8-30** API NUMBER 15- 151-21,792 -0000  
SW SE NE, SEC. 20, T. 7 26 S, R. 12 W/2  
2970 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9232  
Operator: Timberline Oil & Gas Corporation  
Name & Address 4447 S. Canyon Rd., Ste. 1  
Rapid City, SD 57702

Lease Name Studley Well # 1  
County Pratt  
Well Total Depth 4321 140.43 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 30 Month: 8 Year: 19 94

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Wells: 5 1/2" at 4320' w/200 sx cement, PBTD 4296', Perfs at 4142-78'  
1st plug sand back to 4090' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11 a.m. Day: 30 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4090' and dumped 5 sx cement on top of  
sand bridge through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, and 100 sx cement.

No wiper plug-had to use plate and collar on surface pipe due to bad threads in 8 5/8".  
Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2533' of 5 1/2" casing.

**INVOICED**

DATE SEP 12 1994

INV. NO. 41199

(If additional description is necessary, use BACK of this form.)  
observe this plugging.  
Signed Stephen J. Pfeifer  
(TECHNICIAN)