


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Pratt County. Sec. 13 Twp. 26 Rge. 14w E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW/SW/NE

Lease Owner R & K Oil & Gas, Inc.
Lease Name Gee Well No. 1

Office Address Box 866, Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole)

Oil
Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced November 1 1980
Plugging completed November 10, 1980

Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4466
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	370'	None
				4-1/2"	4368'	2795.73'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dump sand to 4150' and four (4) sacks cement. Shot casing at 3900', 3700', 3500' and 3400'.
Pulled 15 joints 4-1/2" casing. Pipe stuck at 2800' when casing unloaded.
Measured in to bridge at 2100'... Halliburton pumped out bridge.
Shot casing at 2700', 2600', 2500', 2400', 2300' and 2200'. Pulled 35 joints of 4-1/2" casing.
Pulled 20 joints 4-1/2" casing for a total of 70 joints. Squeezed well with four (4) sacks hulls, thirty (30) sacks gel, two (2) sacks hulls and 125 sacks 50/50 pozmix with 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold, Box 698, Great Bend
(Address) KS 67530

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1980

My commission expires September 27, 1981

Ruth L. Sloan
Ruth L. Sloan Notary Public.
STATE OF KANSAS

NOV 20 1980
CONSERVATION DIVISION
Wichita, Kansas