

15-151-21266-DD-DD

STATE OF KANSAS -  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 17 TWP. 26S RGE. 14 EW  
Location as in quarters or footage from lines:  
C SE NW

	*		
	17		

Locate Well  
correctly on above  
Section Platt.

Lease Owner Mid-Continent Energy Corporation  
Lease Name McKelvey Well No. 1  
Office Address 120 S. Market, 120 Bldg., Suite 712, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 4/1/83  
Application for plugging filed 4/1/83  
Plugging commenced 4/1/83  
Plugging completed 4/1/83  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,335'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface			8-5/8"	372'	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cmt. - 50/50 Pozmix; 4% gel, 3% CC  
1st plug @ 930' w/50 sks. cmt., 2nd plug set @ 420' w/40 sks. cmt.,  
Final plug @ 40' w/10 sks. cmt. w/solid bridge & wood plug. Circ. 15 sks. thru  
rathole. Cmt'd. water well w/5 sks. Job Completed @ 3:15 P.M.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Wheatstate Oilfield Services, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Larry P. Schneider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
120 S MARKET WICH, KS.  
(Address)

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of April, 19 83

My Commission expires: \_\_\_\_\_



[Signature]  
RECEIVED Notary Public.  
STATE CORPORATION COMMISSION

MAY 02 1983

CONSERVATION DIVISION  
Wichita, Kansas



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG

Mc Kelvey # 1  
 C SE NW Sec. 17-26S-14W  
 Pratt County, Kansas  
 Commenced : 3-24-83  
 Completed : 4-01-83  
 Operator : Mid-Continent Energy Corporation

Depth	Formation	Remarks:
From To		Started drilling 3-24-83.at 10:00 P.M. Drilled to 381'. Set 8 joints, 319.93' 8 5/8", 20# and 1 joint, 41.07', 24#, 361' total, set @ 372'. Cemented with 275 sxs 60-40 poz, 2% gel, 3% CC. Plug down @5:00 A.M. on 3-25-83. Cement did cir. Cement by Sun tkt. # 14550.
-0- 381	Surface clay, sand and shale	
381 1450	Clay, sand, shale	
1450 4335	Lime & Shale	

RECEIVED  
 STATE CORPORATION COMMISSION

APR 11 1983

CONSERVATION DIVISION  
 Wichita, Kansas

T. D. 4335'. Plugged well with 120 sxs 50/50 poz, 4% gel, 3% CC as follows: 50 sxs @ 930', 40 sxs @420', 10 sxs and solid bridge plug @40', 15 sxs cir. in rat hole, 5 sxs in water well. Plug down @3:15 P.M. on 4-01-83. Bob Tarbutton state plugger and cement by Sun, tkt. # 14598.


STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*L. R. Belding*  
 L. R. BELDING VICE-PRESIDENT

My Commission Expires:  
 April 23, 1983



*Darlene Butts*  
 Notary Public