


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 22 Twp. 26S Rge. 14W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SE

Lease Owner Dunne-Gardner Petroleum, Inc.
Lease Name Carr Farms Well No. 1
Office Address Suite 250, 200 West Douglas, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plat

Date Well completed October 8, 1978
Application for plugging filed October 8, 1978
Application for plugging approved October 8, 1978
Plugging commenced October 8, 1978
Plugging completed October 8, 1978

Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4575'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 540; 40 sacks cement
Mud to 330; 40 sacks cement
Mud to 40; plug, 12 sacks cement
3 sacks cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1978

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Donald E. Hunt (employee of owner) ~~owner~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald E. Hunt
Suite 250, 200 West Douglas, Wichita, KS
(Address)

DESCRIBED AND SWORN TO before me this 19th day of October, 1978



Kathleen L. Durbin
Kathleen L. Durbin Notary Public.

DRILLERS LOG

#1 Carr Farms
NW NW SE Section 22-26S-14W
Pratt County, Kansas

OPERATOR: DUNNE-GARDNER PETROLEUM, INC.
Suite 250, 200 West Douglas
Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.
Suite 250, 200 West Douglas
Wichita, Kansas 67202

COMMENCED: September 30, 1978

COMPLETED: October 8, 1978

CASING RECORD: 8-5/8" @ 320' w/260' sx

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	320	Sand, shale and red bed
320	959	Red bed and shale
959	975	Anhydrite
975	1550	Shale and shells
1550	2043	Shale
2043	2675	Lime and shale
2675	2875	Shale, lime and sand
2875	3250	Lime and shale
3250	3485	Shale
3485	4055	Lime and shale
4055	4575	Lime
4575		Rotary total depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1978
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt
Donald E. Hunt

Subscribed and sworn to before me this 19th day of October, 1978.

My appointment expires:
January 4, 1981

Kathleen L. Durbin
Notary Public

